
PART# 600115 2014-2015 Camaro SS 6.2L AR3 Cat Back





Tools Required: 15mm Socket Ratchet Spray lubricant

Caution! Never work on a hot exhuast system. Burns or other serious injuries can result. Always allow the exhaust system to cool before removal. Always consult vehicle manual for proper lifting and support guidelines. Always wear approved saftey glasses when working. Serious injury or death can result if saftey precaustions are not followed.

Removal of factory equipment:

Step 1: Raise and support Vehicle. Loosen the 2 exhaust clamps at the front of the exhaust system.

Step 2: Spary the factory exhaust hangers with spray lubricant to aid in removal

Step 3: Working from the front of the vehicle to the back, remove the factory exaust from the isolators. When all hangers are free lower the front of the exhaust down and carfully guide the exahust assembly out of the vehicle.

NOTE: Save all factory clamps and rubber isolators, they will be reused in the installation of your new system.

Installation of new exhaust

Step 4: Use the provided picture as a guide. Install the "S" pipes onto the short ends (equal length) of the x pipe assembly with an accuseal clamp on each side. The longer side of the x pipe is the passenger side. Do not tighten clamps at this time.

Step 5: Using the factory clamps, slide the x pipe assembly from the previous step onto the factory manifolds with the long side of the x pipe twards the driver side. Place an accuseal clamp on each end of the x pipe and slide the intermediate tubes onto the x pipe (The shorter tube goes to the long side of the x pipe).

Step 7: Slide an accuseal clamp onto each intermediate tube and slide the stub pipes onto the intermediate tubes.slide the hangers into the factory rubber isolators.

Step 8: place an accuseal clamp onto each muffer assembly and slide the expanded end of the muffler assembly onto the stub pipe. slide hanger rod into the rear factory rubber isolators.

Step 6: Slide the accuseal clamps into position, center the exhaust tip in the rear valence opening and snug all exhaust clamps. Check final position and working from back to front torque exhaust clamps to 35 ft-lbs. it may be nessesary to readjust the exhaust and retighten the clamps after the initial 20 mile drive cycle.

Note: After initial startup a small trace of smoke may be visable from the exhuast, do not be concerend. This is from residual oils left in the tube from the manufacturing process and will disipate quickly.

Quick Time Perforance recomends professional installation on all of our products. For technical support please call 973-513-9955 or email tech@quicktimeperformance.com