
E4-VL-23 Three Steel 2-3 Shift Valves

Replacement 2-3 Shift valve for Casting code F6 E4OD and 4R100 valve bodies. Fixes repeated stuck 2-3 shift valve that causes no 3rd or 4th but reverse is OK.




Fits Valve bodies with 2 or 3 SMALL balls located in this area and has F6 code the on main VB.

Remove old 2-3 valve and spring. Re-use retainer. Install New TransGo® Valve and Blue Spring.







02 Apr 09